BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
Schedule-B

NAME OF THE WORK: Construction of RCC drain Near Old Junjappa Temple Surrounding area & Other roads, Mallasandra in Ward No.13, in Shettyhalli Sub Division.

Sl. No	Description of work	Unit	Qty	Approved Sanctiioned Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	KSRRB 300-3. Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3. Page No. 141/ Item No. 19.1/ PWD SR 2015-16	Cum	459.72	83.16	Rupees Eighty Three and Sixteen Paise Only
2	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.3 Page No.12/ Item No. 4.3/ PWD SR 2015-16	Cum	84.60	5070.60	Rupees Five Thousand Seventy and Sixty Paise Only
3	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with with 20mm and down size graded granite metal, coarse aggregate @ 0.69 cum and fine aggregates @ .460cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafairmed -2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings,pedastals,retaining walls, staircase, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.5 ,P.13/I.4.11/ PWD SR 2015-16	Cum	246.09	6198.12	Rupees Six Thousand One Hundred Ninety Eight and Twelve Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Number of Corrections

Executive Engineer
Dasarahalli Division

4	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3, TMT bars Fe 500. Page No. 17/ Item No. 4.46.2/ PWD SR 2015-16	Qtls	147.65	6851.31	Rupees Six Thousand Eight Hundred Fifty One and Thirty One Paise Only
5	Providing & laying cement concrete using 20mm and down size granite coarse aggregate and fine aggregate of ready mixed concrete RMC M20 for RCC works laid in 15cm thick layers and well compacted vibrating,curing,for raft foundation column footing,main and secondary beams with all lead and lift etc,complete (exclusive of cost of steel and fabrication charges Page No.18/ Item No. 4.48/ PWD SR 2015-16		92.70	6332.04	Rupees Six Thousand Three Hundred Thirty Two and Four Paise Only
6	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater dubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift. Page No.174/ Item No.22.7/ PWD SR 2015-16	Sqm	594.00	97.20	Rupees Ninety Seven and Twenty Paise Only
7	Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade,coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. for concrete pavement Page No.175/ Item No.22.8, 22.8.1/ PWD SR 2015-16	Rmt	46.50	124.20	Rupees One Hundred Twenty Four and Twenty Paise Only
8	KSRB 4-6.9: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walss at any thickness,including attached pilasters,buttresses, plinth and string courses cost of all materials, labour complete as per specification. Specification No. KSRB 4.6.9. exceeding 1m in depth. Page No. 15/ Item No. 4.31/ PWD SR 2015-16	Sqm	2259.60	306.72	Rupees Three Hundred Six and Seventy Two Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 01

Signature of the Contractor

Number of Corrections

Executive Engineer
Dasarahalli Division